

Sustainability Appraisal of the Medway Local Plan

Volume 1 of 3: Non-technical summary

DRAFT

June 2025



Sustainability Appraisal of the Medway Local Plan

Volume 1 of 3: Non-Technical Summary of the Regulation 19 SA

LC-1091 Document Control Box	
Client	Medway Council
Report title	Sustainability Appraisal of the Medway Local Plan – Volume 1 of 3: Regulation 19 SA Non-Technical Summary
Status	Final Draft
File name	<u>LC-1091_Vol_1of3_Reg19_SA_Medway_NTS_10_180625LB.docx</u>
Date	June 2025
Author	GW
Reviewed	LB
Approved	ND

Front Cover: [Aerial view of Rochester, Medway – Alexey Fedorenko \(shutterstock\)](#)

Contents of the NTS

1	Introduction.....	N2
2	Purpose and content of the Regulation 19 SA Report.....	N7
3	Baseline and key sustainability issues for the MLP area.....	N9
4	SA methodology.....	N15
5	Reasonable alternatives.....	N17
6	The preferred approach	N29
7	Likely significant effects on the environment	N34

Figures

Figure N.1.1: Sustainable development.....	N3
Figure N.1.2: Sustainability Appraisal and the Local Plan process	N4
Figure N.1.3: Medway Local Plan area.....	N5
Figure N.1.4: The MLP and SA process so far	N6
Figure N.5.1: Definitions for the different types of reasonable alternatives assessed in the SA process.....	N17
Figure N.5.2: The identification, description and evaluation of reasonable alternatives considered throughout the plan-making process.....	N18
Figure N.5.3: Map showing the indicative broad areas covered by each Spatial Delivery Option.....	N23
Figure N.5.4: Summary of generalised positive and adverse effects of reasonable alternative sites.....	N28

Tables

Table N.3.1: Summary of key issues in Medway and the likely evolution of the environment without the MLP ...	N9
Table N.4.1: Summary of the SA Objectives.....	N15
Table N.4.2: Guide for likely significant effects	N16
Table N.5.1: Growth options identified by Medway Council at the Regulation 18 stage	N19
Table N.5.2: Growth options identified by Medway Council at the Regulation 19 stage	N20
Table N.5.3: Spatial delivery options identified by Medway Council	N21
Table N.5.4: Impact matrix of the spatial delivery options (extracted from the Regulation 18 Interim SA Report)	N22
Table N.5.5: Spatial growth options identified by Medway Council	N24
Table N.5.6: Impact matrix of spatial growth options (extracted from the Regulation Interim SA Report)	N25
Table N.6.1: Summary of policy assessments (extracted from Appendix H).....	N29
Table N.6.2: Summary of site policy assessments (extracted from Appendix K)	N33
Table N.7.1: Summary of identified impacts, mitigation and residual effects of the Medway Local Plan.....	N35
Table N.7.2: Proposals for monitoring adverse sustainability impacts of the MLP	N46

1 Introduction

The purpose of this report

- N1. Lepus Consulting Ltd (Lepus) has been instructed by Medway Council to undertake a Sustainability Appraisal (SA) process, incorporating the requirements of Strategic Environmental Assessment (SEA), for the Medway Local Plan (MLP) 2026/27-2040/41.
- N2. The Regulation 19 SA Report has been prepared to present details of the SA process to date and inform Medway Council's preparation of the MLP. This document comprises a Non-Technical Summary (NTS) of the Regulation 19 SA, which presents an assessment of the likely sustainability impacts of proposals set out in the Plan.
- N3. This NTS document comprises **Volume 1** of the SA; it is accompanied by **Volume 2**: The Main SA Report and **Volume 3**: Appendices to the main SA Report.

The Medway Local Plan

- N4. The Medway Local Plan (MLP) sets out the overall strategy for development in Medway Council for the Plan period 2026/27 to 2040/41, providing a framework for where and how new development can take place.
- N5. The MLP aims to strengthen Medway's position in the economy and culture of the region, connected to its surrounding coast and countryside, with a thriving economy, where residents enjoy a good quality of life and there is a clear strategy for addressing climate change and strengthening natural assets.
- N6. The strategic objectives of the Plan are built around the components of economic, social and environmental sustainability, with a cross-cutting aim for infrastructure investment and the development of an intrinsic value which boosts pride in the local area.

What is Sustainability Appraisal and Strategic Environmental Assessment?


- N7. The Planning and Compulsory Purchase Act¹ requires a sustainability appraisal to be carried out on development plan documents in the UK. Additionally, the Environmental Assessment of Plans and Programmes Regulations² (SEA Regulations) require an SEA to be prepared for a wide range of plans and programmes, including development plan documents, to ensure that environmental issues are fully integrated and addressed during decision-making.
- N8. SA is the process of informing and influencing the preparation of a local plan or development plan document to optimise its sustainability. SA considers the social, economic and environmental performance of the plan. The SA (and SEA) can help to ensure that proposals in the plan are appropriate given the reasonable alternatives. It can be used to test the evidence underpinning the plan and help to demonstrate how the tests

¹ Planning and Compulsory Purchase Act 2004. Available at: www.legislation.gov.uk/ukpga/2004/5/contents [Date accessed: 10/01/25]

² The Environmental Assessment of Plans and Programmes Regulations 2004. Available at: www.legislation.gov.uk/ukssi/2004/1633/contents/made [Date accessed: 10/01/25]

of soundness have been met. SA should be applied as an iterative process informing the plan throughout its development.

N9. Sustainability can be defined as “*meeting the needs of the present generation without compromising the ability of future generations to meet their own needs*”³. To be sustainable, development requires the integration of the needs of society, the economy and the environment (see **Figure N.1.1**).



N10. The MLP is at the plan-making stage Regulation 19, known as ‘Publication’ in the Local Plan Regulations 2012⁴, as shown in Stage C of **Figure N.1.2**.

³ Brundtland (1987) Report of the World Commission on Environment and Development: Our Common Future. Available at: <http://www.un-documents.net/our-common-future.pdf> [Date accessed: 09/01/25]

⁴ The Town and Country Planning (Local Planning) (England) Regulations 2012. SI 767




Figure N.1.2: Sustainability Appraisal and the Local Plan process

Medway Local Plan Area

N11. **Figure N.1.3** shows the Medway Council boundary which defines the Plan area for the MLP. Within this area are the five primary towns of Rochester, Chatham, Gillingham, Strood, and Rainham, each boasting unique characteristics and significant heritage features. These towns host the majority of Medway's services, including three universities. Additionally, the authority area encompasses a network of smaller towns and villages.




Figure N.1.3: Medway Local Plan area

The SA process alongside the Medway Local Plan

N12. **Figure N.1.4** provides an overview of the stages that have been undertaken during the preparation of the MLP and accompanying SA outputs, summarising the purpose and content of each.

N13. Each stage included consultation with the statutory bodies for SA/SEA (Historic England, Natural England and the Environment Agency) as well as public consultation with other stakeholders and interested parties. Comments received were considered during the preparation of the SA outputs (see **Appendix C**).




Figure N.1.4: The MLP and SA process so far

2 Purpose and content of the Regulation 19 SA Report

About the Regulation 19 SA Report

N14. The Regulation 19 SA Report presents the overall findings of the SA of the MLP, which is composed principally of 88 strategic, thematic and DM policies and 14 site allocation policies. The SA Report summarises the SA process to date and has been prepared to help inform the examination stage of the MLP.

N15. The purpose of the SA of the MLP is to:

- Identify, describe and evaluate the likely sustainability effects of the MLP proposals and their reasonable alternatives;
- Inform the Council's decision making and preparation of the MLP; and
- Provide an opportunity for statutory consultees, interested parties and the public to offer views on any aspect of the SA.

Structure of the Regulation 19 SA Report

N16. The SA of the MLP is presented in three volumes:

N17. **Volume 1: Non-Technical Summary (NTS)** (this document) provides a summary of the Regulation 19 SA.

N18. **Volume 2: Main SA Report** contains the following chapters:

- **Chapter 1** presents an introduction to this report.
- **Chapter 2** sets out information about the MLP and the SA process to date.
- **Chapter 3** presents the evolution of the environment without the MLP.
- **Chapter 4** sets out the SA methodology.
- **Chapter 5** presents details of the reasonable alternatives considered throughout the SA process.
- **Chapter 6** presents details on the preferred approach as set out in the MLP.
- **Chapters 7 to 15** set out the likely significant effects on the environment, per SEA topic.
- **Chapter 16** summarises the cumulative effects identified.
- **Chapter 17** sets out a range of monitoring recommendations for the MLP.
- **Chapter 18** summarises ways in which the SA has influenced the MLP throughout the plan making process, including through recommendations made in the SA.
- **Chapter 19** outlines the conclusions, residual effects and next steps.

N19. **Volume 3: Appendices** provides further contextual information as follows:

- **Appendix A** presents a review of other relevant policies, plans and programmes (PPPs).
- **Appendix B** presents the SA Framework.

- **Appendix C** summarises the consultation responses received during each stage of the SA process.
- **Appendix D** presents the assessment of two additional growth options (overall quantum of growth) identified since the Regulation 18 stage.
- **Appendix E** sets out the topic-specific methodology and assumptions applied in the evaluation of reasonable alternative sites.
- **Appendix F** presents the assessment of reasonable alternative strategic development sites.
- **Appendix G** presents the assessment of reasonable alternative non-strategic development sites.
- **Appendix H** presents the assessment of MLP strategic, thematic and development management (DM) policies.
- **Appendix I** considers the mitigating influence of MLP policies on reasonable alternative development sites and presents the post-mitigation site assessments.
- **Appendix J** sets out the Council's outline reasons for selection or rejection of each reasonable alternative site considered throughout the SA process.
- **Appendix K** presents the assessment of MLP site allocation policies.

DRAFT

3 Baseline and key sustainability issues for the MLP area

Overview

N20. There are a number of plans, policies and programmes (PPPs) that set out the environmental protection objectives which proposals within the MLP should adhere to (see **Appendix A**). In accordance with the SEA Regulations, the SA process needs to consider these PPPs, as well as existing environmental problems and the baseline characteristics of the local area, in order to determine the likely effects of the local plan itself.

N21. **Volume 2** (the main Regulation 19 SA Report) includes information relating to the baseline and key issues for Medway, drawing on information gathered during the Scoping stage, relating to the following sustainability topics (which incorporate the topics identified in Schedule 2 of the SEA Regulations⁵):

- Air;
- Biodiversity, flora and fauna;
- Climatic factors;
- Cultural heritage;
- Human health;
- Landscape;
- Population and material assets; and
- Soil and water resources.

N22. The SEA Regulations also requires the Environmental Report to present *“information on the relevant aspects of the current state of the environment and the likely evolution thereof without implementation of the plan or programme”*.

N23. Without the MLP, no new plan-led development would occur within the Medway area over and above that which is currently proposed in the adopted Medway Plan 2003⁶. In this scenario, there is more uncertainty in terms of the nature and scale of development that may come forward. In a ‘no plan’ scenario, other PPPs will continue to be a material consideration in planning decisions and legislative protection will continue to be in place.

N24. An overview of each topic, including the key issues affecting Medway and the likely evolution of the baseline within Medway in the absence of the MLP, taking into account information gathered at the scoping stage as well as more up-to-date data and statistics is provided in **Table N.3.1**.

Table N.3.1: Summary of key issues in Medway and the likely evolution of the environment without the MLP

⁵ Schedule 2 of the SEA Regulations identifies the likely significant effects on the environment, including “issues such as (a) biodiversity, (b) population, (c) human health, (d) fauna, (e) flora, (f) soil, (g) water, (h) air, (i) climatic factors, (j) material assets, (k) cultural heritage including architectural and archaeological heritage, (l) landscape and (m) the interrelationship between the issues referred to in sub-paragraphs (a) to (l).”

⁶ Medway Council. Medway Local Plan 2003. Available at: www.medway.gov.uk/downloads/file/2400/medway_local_plan_2003 [Date accessed: 10/01/25]

Theme	Key issues	Likely evolution without the MLP
Air	<ul style="list-style-type: none"> The principal pollutant affecting air quality in Medway is nitrogen dioxide (NO₂), mostly originating from road traffic - reduction in NO₂ emissions is required. There are areas of poor air quality within Medway including the strategic road network and AQMAs, and proximity of residential development to pollutants. The rate of mortality attributable to particulate matter air pollution in Medway is higher than England's average. 	<ul style="list-style-type: none"> Primary sources of air pollution in the UK include road transport, industry, imports and agriculture. These sources will not be expected to change. Congestion issues around Rochester, Chatham, Rainham, Strood and Gillingham, and on the A228 near Hoo, could potentially be exacerbated due to a rising population. Medway is also affected by development outside the boundary, for example, implications of the proposed Lower Thames Crossing, development in neighbouring authority areas, and key junctions in the wider area. Traffic and congestion can have implications for air quality, human health and wildlife, especially those within 200m of main roads. There are four AQMAs within and around Medway and the principal pollutant affecting air quality is nitrogen dioxide (NO₂), mostly sourced from road traffic. Continuing to monitor air quality, especially within AQMAs, and implementation of measures outlined in Air Quality Action Plans will ensure that objectives are in place to decrease exceedances over time. National trends suggest there is an increasing uptake of lower emission vehicle types, such as electric cars, which will be likely to help limit road transport associated emissions in the MLP area and will be likely to further improve air quality.
Biodiversity, Fauna and Flora	<ul style="list-style-type: none"> Medway has a rich natural environment including expansive areas of nature conservation habitats which support rare and important species. Medway's environmental designations and countryside (including agricultural land) is at threat of being compromised to meet housing demand. It is essential that the Green Infrastructure provision and its accessibility is improved, conserved and enhanced to support the envisaged increase in population and accompanying housing provision. 	<ul style="list-style-type: none"> Sites designated for their national and international biodiversity and/or geodiversity value will continue to benefit from legislative protection. Long-term prospects for protecting and enhancing the wealth of habitats and species in the area, and for further developing the existing Green Infrastructure network, would be reduced without a strong policy framework being established in the Plan. It is uncertain if development will be placed near locally designated sites without the introduction of the Plan. Without the Plan, it may be difficult to help ensure that development is not of a type, scale and location that could potentially have a major adverse impact on either a biodiversity or geodiversity designation (of international, national or local significance) or on the

Theme	Key issues	Likely evolution without the MLP
	<ul style="list-style-type: none"> Key issues relating to the Birds and Habitats Directives: Likely significant effects (LSEs) have been identified in the Habitats Regulations Assessment (HRA) screening process for the MLP: air quality, hydrology, recreational pressure and urbanisation impacts at several designations including the Medway Estuary and Marshes SPA and Ramsar, Thames Estuary and Marshes SPA and Ramsar, The Swale SPA and Ramsar, and North Downs Woodlands SAC. 	<p>functioning ecological network of the Plan area and the various essential ecosystem services this provides.</p>
Climatic Factors	<ul style="list-style-type: none"> Medway is a coastal authority and therefore at risk of flooding and sea level rise. Increased number of vehicles on the road will exacerbate congestion, which is likely to be the major source of greenhouse gas emissions within Medway. GI should be enhanced and expanded to maximise ecosystem services and climate resilience. New development needs to incorporate energy efficiency measures and climate change adaptive features in order to respond to predicted levels of climate change. 	<ul style="list-style-type: none"> Carbon dioxide (CO₂) emissions in the transport sector may be likely to rise in line with local trends. An increasing uptake of electric vehicles, a trend seen across the UK, may help to alleviate these issues. The risk of flooding will be likely to increase over time due to the changing climate, increasing the occurrence of extreme weather events. The risk of surface water flooding will depend on the size, nature and extent of non-porous built surface cover in the future, and the effectiveness of the existing drainage system. Total carbon emissions are expected to continue to decrease over the longer term as renewable energy becomes an increasingly competitive force in the UK energy market. Technological advances, which may include renewable energies, electric vehicles, and efficient electricity supplies, will be expected to occur. The lack of a planned growth strategy could lead to increased carbon emissions as development may be less likely to be in sustainable locations.
Cultural Heritage	<ul style="list-style-type: none"> Medway's rich heritage is at threat of being compromised to meet housing demand. There are numerous historic buildings that are listed. Medway includes heritage assets identified as heritage at risk. Archaeological remains, both seen, and unseen have the potential to be affected by new development areas. 	<ul style="list-style-type: none"> National and local guidance seeks to protect designated assets and their settings such as Listed Buildings, Conservation Areas, Scheduled Monuments, and Registered Parks and Gardens. The Heritage at Risk Register will continue to be managed by Historic England who will continue to work with stakeholders to protect these assets.

Theme	Key issues	Likely evolution without the MLP
		<ul style="list-style-type: none"> Further heritage assets are likely to be identified in the future, with or without the MLP. It is uncertain if connectivity with places, local distinctiveness and culture would be emphasised and protected in the absence of the MLP as it is anticipated that the MLP will require a Heritage Statement and/or Archaeological Desk-Based Assessment to be prepared to accompany future planning applications, where appropriate.
Human Health	<ul style="list-style-type: none"> The increasing population in Medway will place pressure on the capacity of health infrastructure and leisure facilities without careful planning and integration of new infrastructure, especially in light of Medway's existing high patient-to-GP ratio. The life expectancy of men and women is anticipated to rise over time, in line with national trends, leading to a greater proportion of older residents with specific needs for housing and services. Residents in Medway have a slightly higher than average proportion of overweight adults and lower average life expectancy in comparison to the South East average and national average. 	<ul style="list-style-type: none"> The population across Medway is expected to continue to increase. This is likely to place greater pressure on the capacity of key services and amenities, including health and leisure facilities and housing. The life expectancy of men and women is anticipated to rise over time, leading to an increasingly aging population. Some residents will continue to need to travel relatively far, likely by driving, to reach important health facilities and services. Dependent on behavioral patterns in society and the future policy approach to the concentration of late-night activities, the spatial patterns of higher crime in the town centres seem likely to continue. There could potentially be a rise in homelessness due to an unmet housing need. Noise pollution from Rochester Airport and existing and new main roads is likely to remain a long-term issue.
Landscape	<ul style="list-style-type: none"> Development has the potential to impact on the Kent Downs National Landscape. There is limited land available for development which places increasing pressure on natural assets due to the projected population increase. Development should maintain important aspects of Medway's varied landscapes, including historic parks and gardens and areas of high landscape value. Development should have regard to the findings of the published Landscape Character Assessment. 	<ul style="list-style-type: none"> The London Green Belt will continue to benefit from legislative protection. The extent to which development will seek to conserve and enhance the character of local landscape and townscapes is uncertain. In the absence of MLP-led development, there could potentially be a rise in the quantity of new development which discords with the local character by altering the style and scale of development.

Theme	Key issues	Likely evolution without the MLP
	<ul style="list-style-type: none"> Change to and impacts upon the views from sensitive landscapes, local residents and the PROW network. Alterations to the urban/rural fringe and increased risk of coalescence between settlements. Increasing demand for housing results in increased pressure on landscapes to accommodate new growth. 	
Population and Material Assets	<ul style="list-style-type: none"> The increasing population within the Plan area will inevitably create more waste and pollution It is important to ensure waste management accords with the waste hierarchy and reduces the overall quantity of waste Waste facilities will need to be provided to cater for a growing population, prevent fly tipping and increase recycling rates Need to provide suitable housing for a growing elderly population Many pockets of economic/income deprivation, with some suffering severe, multiple deprivation Public transport and sustainable travel options are less widespread in more rural areas of the Plan area. The distance and accessibility to key services and amenities, as well as employment opportunities, should be considered when determining where to locate new development. Travel time and sustainable accessibility to educational facilities including primary schools, secondary schools and further/higher level educational facilities varies across the Plan area. 	<ul style="list-style-type: none"> The population of Medway is expected to continue to increase, which will be likely to result in secondary effects. Some of these secondary effects could include effects on health, education and social inequalities due to poorer accommodation and the potential for fewer sustainable travel choices being available. Energy consumption in all sectors is expected to increase. There will be less planning control over the location of future development sites, with potential for planning applications for new homes being allowed in unsustainable locations and/or without necessary supporting infrastructure. There is the potential for the required infrastructure to support further growth not being delivered and for more dispersed patterns of development which could occur without a plan, both of which could increase the proportion of the population with poor access to services.
Soil	<ul style="list-style-type: none"> The majority of land within the plan area is high quality agricultural land including ALC Grade 1 which may be under threat from new development. The development of sites could cause soil erosion and soil loss. 	<ul style="list-style-type: none"> Soil is a non-renewable resource that will be likely to continue to be lost. Rates of soil erosion and loss of soil fertility will be likely to continue to rise due to the impacts of agriculture and climate change.

Theme	Key issues	Likely evolution without the MLP
Water	<ul style="list-style-type: none">The Plan area contains SPZ1, SPZ2 and SPZ3 to the south of the plan area, supporting groundwater resources, the quality and quantity of which should be conserved.There are a number of important water resources and marine habitats within and around Medway which are sensitive to pollutants.The River Medway is a valued asset that is underused. However, development and/or use of the river must not compromise the marine life and ecosystems.Medway lies within an area of water stress, where there is a risk of drought with implications for both human and ecosystem health.	<ul style="list-style-type: none">Without the MLP, there could potentially be less control over the location and scale of new developments with potential to result in over-capacity issues at wastewater treatment works (either cumulatively or individually).In the absence of MLP-led development, the efficiency and sustainability of water consumption may be unlikely to improve owing to the likely increase in population and associated water demand, depending on the nature of any future changes to national regulations, such as the Building Regulations and any emerging policy / regulations relating to water neutrality.Water abstraction, consumption and treatment in the local area will continue to be managed by the Environment Agency and water companies through the Thames and south east RBMPs, WRMP and CAMS in line with the EU Water Framework Directive.

DRAP

4 SA methodology

The SA Framework

N25. Taking into consideration the key issues discussed in **NTS Chapter 3** above, an SA Framework was established which includes SA Objectives, decision-making criteria and indicators. The SA Framework provides a way in which sustainability effects can be described, analysed and compared, and for monitoring the implementation of the Plan.

Table N.4.1: Summary of the SA Objectives

SA Objectives		Relevance to SEA Regulations – Schedule 2
1	Climate Change Mitigation: Minimise Medway's contribution to climate change.	Climatic factors
2	Climate Change Adaptation: Plan for the anticipated impacts of climate change.	Climatic factors, soil, water
3	Biodiversity and Geodiversity: Protect, enhance and manage the flora, fauna, biodiversity and geodiversity assets of Medway.	Biodiversity, flora and fauna
4	Landscape and Townscape: Conserve, enhance and manage the character and appearance of the landscape and townscape, maintaining and strengthening their distinctiveness.	Landscape and cultural heritage
5	Pollution and Waste: Reduce waste generation, increase the reuse and recycling of materials whilst minimising the extent and impacts of water, air and noise pollution.	Air, water, soil, human health and material assets
6	Natural Resources: Protect, enhance and ensure the efficient use of Medway land, soils and water.	Soil, water and material assets
7	Housing: Provide a range of housing to meet the needs of the community.	Population
8	Health and Wellbeing: Safeguard and improve the physical and mental health of residents.	Population and human health
9	Cultural Heritage: Conserve, enhance and manage sites, features and areas of historic and cultural importance.	Cultural heritage
10	Transport and Accessibility: Improve the choice and efficiency of sustainable transport in Medway and reduce the need to travel.	Climatic factors and material assets
11	Education: Improve education, skills and qualifications in Medway.	Population
12	Economy and Employment: Support a strong, diverse, vibrant and sustainable local economy to foster balanced economic growth.	Population and material assets

N26. The full SA Framework used throughout the SA process including indicators is presented in **Appendix B**, with a summary of the 14 SA Objectives shown in **Table N.4.1**. It should be noted that the order of SA Objectives does not infer any prioritisation.

Significant effects

N27. A single value from **Table N.4.2** has been allocated to each SA Objective for each reasonable alternative, option or policy evaluated in the SA process. Justification for the classification of the impact for each SA objective is presented in an accompanying narrative assessment text for all SA assessments.

N28. The assessment of impacts and subsequent evaluation of significant effects is in accordance with Schedule 2 (6) of the SEA Regulations, where feasible, which states that the effects should include: “*secondary, cumulative, synergistic, short, medium and long-term effects, permanent and temporary effects, positive and negative effects, cumulative and synergistic effects*”.

Table N.4.2: Guide for likely significant effects

Significance	Definition (not necessarily exhaustive)
Major Negative --	The size, nature and location of a development proposal will be likely to: Permanently degrade, diminish or destroy the integrity of a quality receptor, such as a feature of international, national or regional importance; Cause a very high-quality receptor to be permanently diminished; Be unable to be entirely mitigated; Be discordant with the existing setting; and/or Contribute to a cumulative significant effect.
Minor Negative -	The size, nature and location of development proposals will be likely to: Not quite fit into the existing location or with existing receptor qualities; and/or Affect undesignated yet recognised local receptors.
Negligible 0	Either no impacts are anticipated, or any impacts are anticipated to be negligible.
Uncertain +/-	It is uncertain whether impacts will be positive or adverse.
Minor Positive +	The size, nature and location of a development proposal will be likely to: Improve undesignated yet recognised receptor qualities at the local scale; Fit into, or with, the existing location and existing receptor qualities; and/or Enable the restoration of valued characteristic features.
Major Positive ++	The size, nature and location of a development proposal will be likely to: Enhance and redefine the location in a positive manner, making a contribution at a national or international scale; Restore valued receptors which were degraded through previous uses; and/or Improve one or more key elements/features/characteristics of a receptor with recognised quality such as a specific international, national or regional designation.

N29. Limitations, assumptions and topic-specific methodologies applied in the SA are discussed in further detail within **Chapter 4** of the Regulation 19 SA Report (**Volume 2**) and **Appendix E (Volume 3)**.

5 Reasonable alternatives

Preface

N30. The SEA Regulations state that when preparing an environmental report, the local plan making process must identify, describe and evaluate reasonable alternatives.

N31. There is no specific definition of a 'reasonable alternative'. Medway Council has identified reasonable alternatives for the MLP at different stages of the plan making process, including different types of reasonable alternatives, including options to meet the required amount of housing, employment and Gypsy and Traveller growth, as well as spatial options and reasonable alternative development sites.

N32. The SA has assessed all options and reasonable alternatives on a comparable basis against the SA Framework to identify likely sustainability impacts, and it is the Council's role to use the SA findings, alongside other evidence base material, to decide which options to 'select' for allocation in the MLP and which to 'reject' from further consideration.

N33. In the case of the MLP, all reasonable alternatives have been identified and described by the Council's plan makers. **Figure N.5.1** below outlines the definitions for the different types of reasonable alternatives assessed throughout the SA process.




Figure N.5.1: Definitions for the different types of reasonable alternatives assessed in the SA process

N34. **Figure N.5.2** summarises the reasonable alternatives considered throughout the SA process, and where these alternatives have been identified, described and evaluated.

Quick guide to reasonable alternatives




Figure N.5.2: The identification, description and evaluation of reasonable alternatives considered throughout the plan-making process

Growth options

N35. Paragraph 62 of the NPPF⁷ states that the minimum number of homes needed in an area should be informed by a local housing need assessment, conducted using the standard method outlined in PPG⁸. The NPPF also states “*any needs that cannot be met within neighbouring areas should also be taken into account in establishing the amount of housing to be planned for*”.

N36. Medway Council identified two reasonable alternatives for the quantum of housing and employment growth to be delivered through the emerging Local Plan (see **Table N.5.1**). These options were based on the latest evidenced needs for the Plan area at the time of writing, and the potential unmet housing needs of the neighbouring authority of Gravesham, noting that these unmet needs were not yet confirmed given Gravesham Borough Council's in-progress Local Plan Partial Review⁹.

N37. The assessment of the two growth options within **Table N.5.1** are presented in full within the Regulation 18 Interim SA Report (2024)¹⁰.

Table N.5.1: Growth options identified by Medway Council at the Regulation 18 stage

Growth option	Description of growth option
Option 1	Meet Medway's Local Housing Need and Initial Objective Assessment of Employment Land Need (based on evidence at Regulation 18 stage). Approximately 22,643 homes and 274,663m² employment land.
Option 2	As for Option 1, plus meeting Gravesham's Unmet Housing Need. Initial consultation and duty to cooperate meetings with Gravesham Borough Council have identified a potential unmet housing need of 2,000 homes. Approximately 24,643 homes and 274,663m² employment land.

N38. Opting for a larger quantum of development tends to result in more significant negative impacts on environmental sustainability objectives. Opting for lower growth could help to reduce pressure on transport systems and social infrastructure. Considering these factors, Option 1 was identified as the best performing option of the two options against the majority of SA Objectives. Conversely, Option 2 was identified as performing stronger against SA Objective 7 (housing) due to its proposal to deliver approximately 2,000 dwellings to address Gravesham Borough's unmet housing need, providing greater benefits regarding affordable housing and the provision of a suitable mix of housing.

N39. The Regulation 18 consultation closed in September 2024. A new version of the NPPF was published in December 2024, alongside updated PPG. New housing figures were

⁷ MHCLG (2024) National Planning Policy Framework. December 2024. Available at: https://assets.publishing.service.gov.uk/media/65829e99fc07f3000d8d4529/NPPF_December_2023.pdf [Date accessed: 31/12/24]

⁸ DLUHC and MHCLG (2024) Planning Practice Guidance. Available at: www.gov.uk/guidance/housing-and-economic-development-needs-assessments [Date accessed: 31/12/24]

⁹ Gravesham Borough Council (2024) Planning Policy News: Gravesham Local Plan Partial Review. Available at: <https://www.gravesham.gov.uk/planning-regeneration/consultations-news/3> [Date accessed: 29/04/25]

¹⁰ Lepus Consulting (2024). Sustainability Appraisal of the Medway Local Plan (2025-2041). Regulation 18 Interim SA Report. June 2024. Available at: <https://medway.oc2.uk/document/20> [Date accessed: 28/11/24]

published, derived through the Standard Method, that sought to meet the government's aspirational target of building 1.5 million homes during this parliamentary term.

N40. The latest Standard Method calculation for Medway is 1,636 dwellings per annum¹¹. Across the proposed 15-year Plan period, this equates to a total housing need of 24,540 dwellings. In terms of employment needs, the 2025 Employment Land Needs Assessment (ELNA) identified a need for a minimum of 204,000 sqm of industrial floorspace and 36,500 sqm of office floorspace (totalling 240,500 sqm).

N41. **Table N.5.2** presents two further reasonable alternative growth options which have been identified by Medway Council in response to the change in Standard Method housing number: Options 3 and 4. These options effectively update Options 1 and 2 as described above so that the latest calculated housing and employment need figures can be evaluated in the SA process. The full evaluation of these options can be found in **Appendix D**.

Table N.5.2: Growth options identified by Medway Council at the Regulation 19 stage

Growth option	Description of growth option
Option 3	Meet Medway's Local Housing Need (based on latest standard method calculation) and Objective Assessment of Employment Land Need. Approximately 24,540 homes and 240,500m² employment land.
Option 4	As for Option 3, plus meeting Gravesham's Unmet Housing Need. Initial consultation and duty to cooperate meetings with Gravesham Borough Council have identified a potential unmet housing need of 2,000 homes. Approximately 26,540 homes and 240,500m² employment land.

Comment from Council:

Gravesham Borough Council has notified Medway Council of an estimated unmet housing need of 2,000 homes through responses to consultations and duty to cooperate meetings. Medway Council has requested further information from Gravesham Borough Council to demonstrate the unmet housing need. Medway Council has not received an assessment of land availability from Gravesham Borough Council, therefore Option 2 and Option 4 cannot be justified. This matter is set out in a Statement of Common Ground.

Option 1 and Option 3 have been shown to perform better compared to Option 2 and Option 4. Option 3 is aligned with the direct output from the Standard Method as a starting point to determine local housing need. Therefore, Option 3 forms the basis of Medway Council's spatial strategy.

Spatial delivery options

N42. Drawing on information gathered through Call for Sites exercises and the Interim Land Availability Assessment (LAA)¹² and sites promoted in response to the previous Regulation 18 consultation (2023), 12 'spatial delivery options' (SDOs) were identified by the Council.

¹¹ Turley (2025) The standard method of assessing housing need. Available at:

https://www.turley.co.uk/sites/default/files/pdf/file/2025-05/turley_lpdf - revised standard method analysis may2025_0.pdf [Date accessed: 13/06/25]

¹² Medway Council (2023) Land Availability Assessment Interim Report, October 2023. Available at:

https://www.medway.gov.uk/downloads/file/8413/medway_land_availability_assessment_september_2023 [Date accessed: 31/12/24]

The 12 SDOs were assessed within Appendix B of the Regulation 18 (2024) Interim SA Report¹³.

N43. The SDOs were based on broad locations across Medway, apart from one which comprises sites for employment land uses only. The broad locations which form the SDOs cover a range of land use types, which could provide a mixture of sites including greenfield and rural development as well as opportunities for regeneration of brownfield land, in order to explore the relative benefits and challenges associated with growth in these areas across Medway.

N44. The 12 SDOs and the likely range of homes that could theoretically be delivered through each SDO are presented in **Table N.5.3**. **Figure N.5.3** presents a map of the indicative broad areas covered by each of the 12 SDOs.

Table N.5.3: Spatial delivery options identified by Medway Council

Spatial delivery option	Minimum number of new homes	Maximum number of new homes
Capstone Valley	3,749	4,336
Chatham Docks	3,000	3,000
Cliffe and Cliffe Woods	2,079	2,406
East of Rainham	1,243	1,432
Hoo Peninsula	10,893	12,970
Medway City Estate	1,092	1,502
Medway Valley	1,264	1,457
North of Rainham	2,560	3,275
North of Strood	2,029	2,319
Suburban	495	779
Urban	7,719	8,542
Employment only	480ha of employment floorspace	480ha of employment floorspace

N45. **Table N.5.4** summarises the SA findings. The assessments are presented in full within Appendix B of the Regulation 18 (2024) Interim SA Report¹⁴.

N46. No single SDO could deliver the required quantum of development and a combination of SDOs would be needed to form a spatial strategy and ensure a sustainable level of growth across Medway as a whole. Drawing on the assessment narrative and relative sustainability performance of the 12 SDOs against each SA Objective, the Urban SDO emerged as the best performing option the most often. The Suburban SDO and Chatham Docks SDO also performed relatively well, each ranking 1st against two SA Objectives. The worst performing SDO is the Hoo Peninsula, ranking the lowest against a number of SA Objectives, with potential adverse effects associated with the introduction of a large quantum of growth in small settlements and in proximity to sensitive ecological receptors.

¹³ Lepus Consulting (2024). Sustainability Appraisal of the Medway Local Plan (2025-2041). Regulation 18 Interim SA Report. June 2024. Available at: <https://medway.oc2.uk/document/20> [Date accessed: 31/12/24]

¹⁴ Lepus Consulting (2024). Sustainability Appraisal of the Medway Local Plan (2025-2041). Regulation 18 Interim SA Report. June 2024. Available at: <https://medway.oc2.uk/document/20> [Date accessed: 31/12/24]

Table N.5.4: Impact matrix of the spatial delivery options (extracted from the Regulation 18 Interim SA Report)

Spatial Delivery Option	1	2	3	4	5	6	7	8	9	10	11	12
	Climate change mitigation	Climate change adaptation	Biodiversity and geodiversity	Landscape and townscape	Pollution and waste	Natural resources	Housing	Health and wellbeing	Cultural heritage	Transport and accessibility	Education	Economy and employment
Capstone Valley	--	0	-	--	-	--	++	-	0	-	--	+
Chatham Docks	--	--	-	0	-	0	++	+	0	++	0	+
Cliffe and Cliffe Woods	-	0	--	-	-	--	+	--	0	--	-	+
East of Rainham	-	0	-	--	-	--	+	--	-	-	+	+
Employment	+/-	--	--	-	-	-	0	--	-	--	0	++
Hoo Peninsula	--	0	--	--	--	--	++	--	--	--	-	+
Medway City Estate	-	--	-	0	--	-	+	-	-	0	-	+
Medway Valley	-	-	--	--	--	-	+	--	-	0	--	+
North of Rainham	--	-	-	--	-	--	++	-	-	0	-	+
North of Strood	-	0	-	--	--	--	+	--	-	0	-	+
Suburban	-	0	-	-	-	0	+	0	0	+	+	+
Urban	--	--	-	0	--	0	++	++	--	++	++	+




Figure N.5.3: Map showing the indicative broad areas covered by each Spatial Delivery Option

N47. A combination of SDOs will be required to form a spatial strategy. The Council has considered different combinations of SDOs which could form spatial growth options.

Spatial growth options

N48. The spatial strategy will direct future growth in Medway for the Plan period to 2040/41.

N49. Given Medway's geography and constraints, including environmental constraints on the Hoo Peninsula and transport constraints within the existing urban areas, the Council is limited in the number of different spatial approaches it can take to accommodate growth.

N50. Drawing on information gathered through Call for Sites exercises and the Interim LAA¹⁵ and sites promoted in response to the previous Regulation 18 consultation (2023), three spatial growth options (which constitute reasonable alternative spatial strategies) have been identified by the Council and are summarised in **Table N.5.5**. All three options could theoretically meet the identified housing and employment needs for Medway, and are based upon a combination of different spatial delivery options.

Table N.5.5: Spatial growth options identified by Medway Council

Option	Characteristics of spatial growth option	Relationship to spatial delivery options
1. Urban Regeneration Focus	<p>The Urban Regeneration Focus spatial growth option is characterised by:</p> <ul style="list-style-type: none"> Urban centres catering for everyday needs and acceptable walking distances to public transport nodes. Maximising development on brownfield sites in urban and waterfront areas by applying an additional 25% (apart from Chatham Docks) to represent densification. Limited greenfield development adjoining existing larger settlements, including Strood, Rainham, Lordswood and Hoo St Werburgh. Employment sites are located close to new urban housing, with industry and <i>sui generis</i> uses at Kingsnorth and the Isle of Grain. <p>Based on a maximum yield calculation, plus an additional 25% (apart from Chatham Docks) to represent densification, this option could accommodate up to 23,710 homes.</p>	<p>The Urban Regeneration Focus spatial growth option comprises the following spatial delivery options:</p> <ul style="list-style-type: none"> Urban (full) Chatham Docks (3,000 homes) Medway City Estate (full) Capstone Valley (partial) East of Rainham (full) Hoo Peninsula (partial) North of Strood (partial) Suburban (full)
2. Dispersed Growth	<p>The Dispersed Growth spatial growth option is characterised by:</p> <ul style="list-style-type: none"> Extensive release of greenfield and Green Belt land, including Hoo Peninsula, North of Rainham, Medway Valley Sites such as Darland and Deangate, where there is the potential for environmental impacts. Limited regeneration where there is not a confirmed or active market interest. Large established employment sites, although the more limited town centre regeneration misses opportunities for mixed use developments. <p>Based on a minimum yield calculation, this option could accommodate up to 25,615 homes.</p>	<p>The Dispersed Growth spatial growth option comprises the following spatial delivery options:</p> <ul style="list-style-type: none"> Urban (partial, i.e. consented developments only) Chatham Docks (employment land uses only) Capstone Valley (full) Cliffe and Cliffe Woods (full) East of Rainham (full)

¹⁵ Medway Council (2023) Land Availability Assessment Interim Report, October 2023. Available at:

https://www.medway.gov.uk/downloads/file/8413/medway_land_availability_assessment_september_2023 [Date accessed: 09/01/25]

Option	Characteristics of spatial growth option	Relationship to spatial delivery options
		<ul style="list-style-type: none"> • Hoo Peninsula (full) • Medway Valley (full) • North of Rainham (full) • North of Strood (full) • Suburban (full)
3. Blended Strategy	<p>The Blended Strategy spatial growth option is characterised by:</p> <ul style="list-style-type: none"> • Urban and new local centres catering for everyday needs and acceptable walking distances to public transport nodes. • Brownfield first with regeneration in town centres and waterfront areas, complemented by suburban and rural areas where development proposals could overcome constraints. • Likelihood of avoiding direct impacts on designations. • Likelihood of providing for the range of housing types for communities. • Density and heights in town centres that are compatible with the Chatham Design Code, other supplementary planning guidance and heritage constraints. • Avoiding coalescence of existing settlement patterns, i.e. maintaining a 'strategic gap'. • Employment sites are located close to new urban housing, with industry and sui generis uses at Kingsnorth and the Isle of Grain. <p>Based on a minimum yield calculation, this option could accommodate up to 23,733 homes.</p>	<p>The Blended Strategy spatial growth option comprises the following spatial delivery options:</p> <ul style="list-style-type: none"> • Urban (full) • Chatham Docks (3,000 homes) • Medway City Estate (full) • Capstone Valley (partial) • Cliffe and Cliffe Woods (partial) • East of Rainham (full) • Hoo Peninsula (partial) • Medway Valley (partial) • Suburban (full)

N51. **Table N.5.6** summarises the SA findings. The assessments and rankings of the spatial growth options are presented in full within the Regulation 18 SA Interim Report¹⁶.

N52. The urban focus of development through Option 1 will expect to reduce reliance on private car use and increase sustainable travel. Option 1 was therefore identified as performing well with regard to a variety of SA Objectives including climate change mitigation (SA Objective 1), landscape and townscape (SA Objective 4), natural resources (SA Objective 6 and transport and accessibility (SA Objective 10). Option 2, while not ranking as the best-performing option against any SA Objective, offers health and well-being benefits due to its dispersed development approach. Furthermore, through a dispersed approach, Option 2 could reduce pressures on existing infrastructure, particularly within urban settlements. Option 3 was identified to provide the most sustainable balance by combining urban regeneration with suburban and rural development, promoting sustainable travel and addressing the needs of diverse communities.

Table N.5.6: Impact matrix of spatial growth options (extracted from the Regulation Interim SA Report)

¹⁶ Lepus Consulting (2024). Sustainability Appraisal of the Medway Local Plan (2025-2041). Regulation 18 Interim SA Report. June 2024. Available at: <https://medway.oc2.uk/document/20> [Date accessed: 31/12/24]

Spatial Growth Option	1 Climate change mitigation	2 Climate change adaptation	3 Biodiversity and geodiversity	4 Landscape and townscape	5 Pollution and waste	6 Natural resources	7 Housing	8 Health and wellbeing	9 Cultural heritage	10 Transport and accessibility	11 Education	12 Economy and employment
1. Urban Regeneration Focus	+	0	-	0	-	+	+	0	0	+	0	+
2. Dispersed Growth	--	-	--	--	--	--	+	0	-	-	-	+
3. Blended Strategy	-	+	0	-	-	-	++	+	0	0	+	++
Best Performing Option?	1	3	3	1	3	1	3	3	3	1	3	3

Comment from Council:

The Regulation 18 (2024) consultation presented three spatial growth options. The third spatial growth option, 'Blended Strategy', was identified as the Council's indicative preferred approach. The Interim SA found that this option is likely to offer the best balance of sustainability considerations to meet Medway's development needs. However, following the Regulation 18 (2024) consultation, the Council's emerging housing trajectory found that the two largest sites could not be expected to be completed by 2041, specifically Mill Fields (LW8) and Chatham Docks (SMI6). A strategic site to the east of Rainham (RSE10) was subsequently rejected following reconsideration the Council's assessment of land availability. No new information about the availability of sites located in town centres was received; there was limited scope to increase densities of sites in these locations. In response to the Regulation 18 (2024) consultation, representations on behalf of the Church Commissioners and Esquire Developments set out compelling cases to allocate more land to the east of Ropers Lane, Hoo St Werburgh (HHH22 & HHH31), and at Lower Rainham (RN9) respectively. Engagement with Gravesham Borough Council led to the reconsideration of three adjoining Green Belt sites to the west of Stood (SNF1, SNF2 and SR5). These sites formed part of the second spatial growth option, 'Dispersed Growth'. Meanwhile, these sites were subsequently deemed suitable, available and achievable, and crucially ensured a housing supply surplus. The final selection of sites still reflects a blended strategy, but it takes account of the outputs of the Council's assessment of land availability.

Reasonable alternative sites

N53. At the Regulation 18 stage, a total of 359 reasonable alternative sites were identified by Medway Council and evaluated in the Regulation 18 Interim SA Report¹⁷. The Council further categorised the 359 reasonable alternative sites, by identifying strategic sites. Strategic residential-led sites are considered to be those which comprise at least 10ha and could deliver at least 500 new homes (or at least 300 homes for sites in Allhallows, Lower Stoke, Middle Stoke, reflecting the scale of growth in these smaller villages). Strategic employment-led sites are considered to be those which comprise over 75ha. At the

¹⁷ Lepus Consulting (2024). Sustainability Appraisal of the Medway Local Plan (2025-2041). Regulation 18 Interim SA Report. June 2024. Available at: <https://medway.oc2.uk/document/20> [Date accessed: 31/12/24]

Regulation 18 stage, 24 reasonable alternative strategic sites were identified, and 335 non-strategic sites.

N54. Following the Regulation 18 consultation in 2024, Medway Council have produced an updated LAA (2025)¹⁸, which led to updated information for a number of non-strategic reasonable alternative sites, including capacity and use changes. The 335 reasonable alternative non-strategic sites comprise:

- 200 sites identified for residential use;
- 47 sites identified for non-residential use;
- 87 sites identified for mixed uses; and
- One site identified for either residential or non-residential use.

N55. The Council also identified two new reasonable alternative strategic sites, and merged two previously assessed strategic sites (Sites HHH2 and HHH31). Furthermore, the Council has provided updated information including capacity changes and change of the proposed site use. Therefore, a total of 27 reasonable alternatives strategic sites have been evaluated, comprising:

- 22 residential-led strategic sites; and
- Five employment-led strategic sites.

N56. The pre-mitigation assessments of the 27 strategic sites are presented within **Appendix F** and the pre-mitigation assessment of the 335 non-strategic reasonable alternative sites is presented within **Appendix G**, superseding the site assessment information presented within the Regulation 18 Interim SA.

N57. **Figure N.5.4** shows how a range of positive and adverse effects were likely to arise from the different reasonable alternative sites, prior to the consideration of the mitigation hierarchy.

¹⁸ Medway Council (2025) Medway Local Plan 2041: Land Availability Assessment, June 2025.



Figure N.5.4: Summary of generalised positive and adverse effects of reasonable alternative sites

Post-mitigation assessments of reasonable alternative sites

N58. Mitigation, using the emerging MLP policies (see **Appendix H** for the SA evaluation of policies), has been applied to the SA results for each reasonable alternative site and presented in **Appendix I**.

N59. Following the application of policy mitigation, it was identified that many of the pre-mitigation adverse effects will likely be reduced or mitigated.

N60. The SA process has been used to evaluate reasonable alternative sites on a comparable basis against the SA Framework to identify likely sustainability impacts. It is the Council's role to use the SA findings, alongside other evidence base material, to decide which sites to 'select' for allocation in the MLP and which to 'reject' from further consideration.

N61. **Appendix J** sets out the outline reasons for selection and rejection of each reasonable alternative site considered throughout the SA process, provided by Medway Council.

6 The preferred approach

MLP Policies

N62. Following comments received during the Regulation 18 consultations and recommendations set out in the SA reports, Medway Council have prepared the Regulation 19 Publication Version of the MLP.

N63. The MLP includes chapters which set out the overarching vision, spatial strategy and 88 strategic, thematic and development management (DM) policies. The MLP also contains 14 site allocation policies, discussed below.

N64. **Table N.5.1** below presents a summary of the assessment of 88 strategic, thematic and DM policies. These policies are generally anticipated to have positive impacts on the SA Objectives, with negative impacts associated predominantly with pollution and waste, climate change mitigation and some for biodiversity and health. Uncertain impacts have mostly been identified where site-specific contextual information is lacking which could positively or adversely impact the chosen SA Objective.

Table N.6.1: Summary of policy assessments (extracted from Appendix H)

Policy ref	SA1 CC Mitigation	SA2 CC Adaptation	SA3 Biodiversity and geodiversity	SA4 Landscape and townscape	SA5 Pollution and waste	SA6 Natural resources	SA7 Housing	SA8 Health and wellbeing	SA9 Cultural heritage	SA10 Transport and accessibility	SA11 Education	SA12 Economy
Vision	++	++	+	+	+	+	++	++	++	++	++	++
SDS	+	+/-	+/-	+	+/-	+	++	+	+/-	+/-	+	++
S1	++	++	+	0	+	+	0	+	0	+	0	+
S2	+	+	+/-	+	+	+	0	0	0	0	0	0
S3	+	+	+/-	+	0	+	-	0	0	0	0	-
S4	+	+	+	++	0	+	0	+	+	0	0	0
S5	+	+	+	+	+	+	0	+	+	+	0	0
S6	+	+	+	++	0	+	0	+	+	0	0	0
DM1	+	++	+	+	+	+	0	+	0	0	0	+
DM2	0	0	+	0	+	+	+	+	0	0	0	0
DM3	0	0	+	0	+	0	0	+	0	0	0	0
DM4	0	0	0	0	+	0	0	+	0	0	0	0
S7	+	+	+	+	0	+	+	+	0	0	0	0
T1	+	+	+	++	0	+	+	+	+	+	+	+
DM5	+	0	+	+	+	0	+	+	0	0	0	0
DM6	+	0	0	+	+	+	+	+	0	+	+	+
DM7	0	0	0	+	0	0	0	0	+	0	0	0
DM8	0	0	0	+	0	0	0	0	0	0	0	0
S8	0	0	0	+	0	0	0	+	++	0	0	0
DM9	0	0	0	+	0	0	0	0	+	0	0	0
S9	+	0	0	+	0	0	0	0	++	+	0	+
DM10	0	0	0	+	0	0	0	0	+	0	0	0
DM11	0	0	0	0	0	0	0	+	0	0	0	0
T2	+	0	0	0	0	0	+	+	0	0	0	+

Policy ref	SA1	SA2	SA3	SA4	SA5	SA6	SA7	SA8	SA9	SA10	SA11	SA12
	CC Mitigation	CC Adaptation	Biodiversity and geodiversity	Landscape and townscape	Pollution and waste	Natural resources	Housing	Health and wellbeing	Cultural heritage	Transport and accessibility	Education	Economy
T3	+	0	0	0	0	0	+	+	0	0	0	0
T4	0	0	0	0	0	0	+	+	0	+	0	0
T5	+	0	0	0	0	0	+	0	0	+	+	0
T6	0	0	0	+	0	0	+	0	0	0	0	0
T7	0	0	+	0	0	0	+	0	0	0	0	0
T8	0	0	0	0	0	0	+	0	0	0	0	0
T9	0	0	0	+	0	0	+	0	0	0	0	0
T10	0	+	+/-	-	+/-	+	+	+	+/-	+	+	0
T11	0	0	0	+	0	0	+	0	0	+	0	+
S10	+/-	+/-	+/-	+/-	-	+/-	0	+/-	+/-	+/-	0	++
S11	0	0	0	0	0	0	0	0	0	0	0	+
S12	+/-	+/-	+/-	+/-	-	+/-	0	+/-	+/-	+/-	0	++
T12	+	0	0	0	+	0	0	+	0	+	++	+
T13	0	+	+	+	0	0	0	+	+	+/-	0	+
S14	0	0	0	+	0	0	0	+	+	+	0	+
T14	0	0	0	0	0	0	0	0	0	+	0	+
S15	+	+	+	+	+	+	0	+	+/-	+	0	++
S16	+	+	+/-	+	+	+	0	+	+/-	+	0	++
T15	+	+	+/-	+	+	+	0	+	+/-	+	0	+
T16	0	0	0	0	0	0	0	0	0	0	0	+
T17	+	0	0	0	0	0	0	+	0	+	0	+
S17	+	0	0	0	0	+	+	+	+/-	+	0	++
S18	+	0	0	0	0	0	0	+	0	0	0	+
S19	0	0	0	+	+	0	0	+	0	+	0	+
S20	+	0	0	+	+	+	0	++	+/-	+	0	++
S21	0	0	0	0	+	0	0	+	0	+	0	+
S22	+	0	0	0	+	0	0	+	0	+	0	+
S23	0	0	0	0	0	0	0	0	0	0	0	+
DM12	+	0	0	+	+	0	0	+	0	+	0	+
T18	+	0	0	0	+	0	0	+	0	+	0	+
T19	0	0	0	+	0	0	0	0	0	0	0	+
DM13	+/-	0	0	0	+/-	0	0	+	0	+/-	0	+
DM14	+/-	0	0	+	+/-	+	0	+	+	+	0	+
DM15	+	0	0	0	+	0	0	+	0	+	0	0
T20	+	0	+/-	+	+	0	0	+	+/-	+	0	0
DM16	+	0	+/-	+/-	+	0	0	+	0	+	0	+
DM17	+	0	0	0	+	0	0	0	0	++	0	+
T21	0	0	0	0	0	+	0	0	+/-	+	0	++
T22	0	0	0	0	0	0	0	0	+/-	0	0	+
T23	0	0	0	0	0	0	0	0	0	+	+	+
T24	+/-	0	0	0	+/-	0	0	0	0	+/-	0	+
T25	+	0	0	+	+	0	0	+	0	+	0	0
T26	+	0	0	0	+	0	0	+	0	+	+	0
DM18	+	0	0	0	+	0	0	+	0	++	+	+
DM19	+	0	0	+	0	+	0	0	0	+	0	+

Policy ref	SA1	SA2	SA3	SA4	SA5	SA6	SA7	SA8	SA9	SA10	SA11	SA12
	CC Mitigation	CC Adaptation	Biodiversity and geodiversity	Landscape and townscape	Pollution and waste	Natural resources	Housing	Health and wellbeing	Cultural heritage	Transport and accessibility	Education	Economy
DM20	+	0	0	+/-	+	0	0	+	0	+	+	+
T27	+	0	0	0	0	0	0	++	0	+	0	0
T28	+	+	+	+	0	0	0	++	0	0	0	0
DM21	+	+	+	+	+	0	0	++	0	+	0	0
T29	+	0	0	0	0	0	0	+	+	+	0	0
S24	+	+	0	++	+	0	0	++	0	++	++	+
DM22	+	0	0	0	+	0	0	0	0	+	+	++
T30	0	0	0	0	0	++	+/-	0	0	0	0	+
T31	0	0	0	0	0	+	+/-	0	0	0	0	+
T32	+	0	-	+	+	+	0	-	+/-	+	0	+
T33	+	0	-	-	-	++	0	-	+/-	+	0	+
DM23	+	0	0	0	++	+	0	0	0	0	0	0
T34	0	0	0	0	+	0	0	0	0	0	0	0
T35	+/-	-	-	-	++	-	0	-	-	-	0	0
T36	0	0	0	0	+	+/-	0	0	0	0	0	0
T37	+	+/-	+/-	+/-	+	+/-	0	+/-	+/-	+/-	0	0
T38	+/-	+/-	+/-	0	+	+/-	0	+/-	+/-	+/-	0	0
T39	+/-	0	0	+	+	+	0	0	+	+/-	0	0
T40	0	0	0	0	+	0	0	0	0	0	0	0
S25	++	--	--	-	+/-	-	0	+/-	-	-	+	++
T41	+	0	0	0	0	0	0	+	0	0	0	0

Site allocations

N65. The SA process has been used to evaluate reasonable alternative sites on a comparable basis against the SA Framework to identify likely sustainability impacts. It is the role of the Council to use the SA findings, alongside other evidence base material, to decide which sites to 'select' for allocation in the MLP and which to 'reject' from further consideration (see **Appendix J** for more details).

N66. A total of 131 sites have been selected for allocation in the MLP by Medway Council. This includes 12 'strategic' sites and 119 'non-strategic' sites.

N67. These sites will collectively result in the delivery of 21,194 homes to meet identified needs (in combination with 1,762 pipeline sites and 1,584 windfall sites) and sufficient land for a portfolio of employment sites that meet the needs of different types of businesses to meet the identified employment land needs (204,000m² industrial and 36,500m² office space, plus account for lack of building stock identified in the ELNA).

N68. As discussed in **Chapter N.5**, all reasonable alternative sites were evaluated in the SA process pre-mitigation (see **Appendix F** for strategic sites and **Appendix G** for non-strategic sites) and post-mitigation (see **Appendix I**). The SA findings were fed back to the Council on an iterative basis to assist in decision-making regarding the selection or rejection of each site within the emerging MLP.

Site allocation policies

N69. In addition to the 88 strategic, thematic and DM policies as outlined above, Medway Council has prepared 14 site allocation policies. Each policy relates to a number of site allocations that have been proposed for inclusion in the MLP, grouped by geographic area.

N70. Each site allocation policy has been evaluated in **Appendix K**, drawing on the post-mitigation site assessments as presented in **Appendix I**. The assessment considers the extent to which the provisions of the 14 site allocation policies will further improve sustainability of these sites, compared to the post-mitigation assessment findings.

N71. The assessment findings are summarised in **Table N.6.2**. The majority of site policies will ensure sustainable access to schools, healthcare, jobs and local services are improved (SA Objectives 8, 10, 11, 12). The policies will ensure that, particularly in the urban areas, opportunities are sought for heritage-led development and regeneration to conserve and enhance the landscape/townscape and historic environment (SA Objective 4 and 9). The majority of sites lie in Flood Zone 1 where fluvial flood risk is low and climate change adaptation measures can be secured via careful integration of GI (SA Objective 2).

N72. However, potential adverse impacts have been indentified in relation to the loss of high-quality agricultural land (SA Objective 6), alteration of rural landscape character (SA Objective 4), and the generation of pollution associated with new development (SA Objective 5). For more rurally located sites, minor negative effects have been identified in relation to transport and access to healthcare (SA Objectives 8 and 10). Some allocations lie within Flood Zones 2 and/or 3, where site-specific flood risk assessments will be required to confirm the potential for mitigation (SA Objective 2).

N73. Uncertainty remains in the assessment against climate change mitigation (SA Objective 1) where there is potential for both positive and adverse effects on GHG emissions associated with the scale of development proposed alongside encouragement for minimising embodied emissions and supporting sustainable energy infrastructure. Additionally, the impacts of all allocations on biodiversity are uncertain at the time of writing, in absence of the HRA conclusions (SA Objective 3). For all policies, the potential impacts on Medway's constrained transport network will need to be carefully considered in light of the findings of the emerging Strategic Transport Assessment.

Table N.6.2: Summary of site policy assessments (extracted from Appendix K)

Policy ref	SA1	SA2	SA3	SA4	SA5	SA6	SA7	SA8	SA9	SA10	SA11	SA12
	CC Mitigation	CC Adaptation	Biodiversity and geodiversity	Landscape and townscape	Pollution and waste	Natural resources	Housing	Health and wellbeing	Cultural heritage	Transport and accessibility	Education	Economy
SA1	+-	0	+-	0	-	0	++	+	0	++	+	+
SA2	+-	-	-	+	-	0	++	+	+	++	+	+
SA3	+-	+	+-	0	-	+	++	+	0	++	+	+
SA4	+-	-	+-	+	-	0	++	+	+	++	+	+
SA5	+-	-	+-	-	-	-	++	+	0	++	+	+
SA6	+-	+	+-	0	-	--	++	0	0	+	++	+
SA7	+-	+	+-	-	-	--	++	0	0	+	++	+
SA8	+-	+	+-	-	-	--	++	-	0	+	++	++
SA9	+-	+	+-	-	-	--	++	-	0	+	+	+
SA10	+-	+	+-	-	-	--	++	0	0	+-	++	+
SA11	+-	-	+-	-	-	--	++	-	0	-	0	+
SA12	+-	-	+-	-	-	-	++	-	0	-	+	+
SA13	+-	+-	-	+-	--	-	++	-	0	+	+	+
SA14	+-	-	+-	-	--	--	0	-	0	-	0	++

DRY

7 Likely significant effects on the environment

Identified impacts, mitigation and residual effects

N74. Proposals in the MLP have been assessed for their sustainability impacts, the results of which are presented in the relevant appendices and/or report chapters as described in the above NTS chapters. The assessment of the MLP, including reasonable alternatives, was undertaken using a combination of available evidence and professional judgement.

N75. **Table N.7.1** provides an overview of the evaluation of the MLP against the SEA topics as provided in the main Regulation 19 SA Report.

N76. The second column of **Table N.7.1** provides a summary of the potential negative impacts of the MLP relating to each of the sustainability themes (as set out in full within **Chapters 7-15** of the main SA Report, **Volume 2**). These are impacts that have been identified prior to the implementation of MLP mitigation.

N77. Column three of **Table N.7.1** summarises the effects of the MLP policies which are expected to mitigate or help to reduce some of the potentially negative impacts.

N78. In some cases, the MLP policies are likely to fully mitigate identified effects or lead to longer term benefits. The MLP policies, however, are not anticipated to fully mitigate all of the identified effects. The residual effects are identified and drawn to the attention of the plan makers and summarised in the final column of **Table N.7.1**.

Cumulative effects

N79. The cumulative effects assessment (CEA) is the process of identifying and evaluating the effects that arise when the total significant effects of the Local Plan and assessed alongside known existing underlying trends and other PPPs.

N80. Cumulative effects are different from effects that occur alone. Alone, the Plan may not result in residual adverse effects for a particular topic, for example the effects of urban sprawl on landscape character, but when considered cumulatively, may result in significant effects that require mitigation or monitoring.

N81. Cumulative effects of the MLP are discussed in **Table N.7.1** alongside the identified residual effects, with the full CEA provided in **Chapter 16** of the main Regulation 19 SA Report.

Table N.7.1: Summary of identified impacts, mitigation and residual effects of the Medway Local Plan

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
 AIR	<ul style="list-style-type: none"> Increased generation of, and exposure to, air pollution, such as NO₂ and particulate matter, from the construction and occupation of new development and associated traffic. Increased pollutant levels can affect respiratory health and lead to adverse effects on vulnerable habitats. 	<ul style="list-style-type: none"> Policy DM3 (Air quality) promotes design to improve emissions, such as electric charging points and low NO₂ boilers. Development which may negatively impact air quality will provide an air pollution impact assessment with mitigation measures, including development in proximity to an AQMA or biodiversity designation. The Spatial Development Strategy, Policy T26 (Accessibility standards) and Policy DM20 (Cycle parking and storage) aim to reduce reliance on cars and need to travel by facilitating sustainable and active transport. Policy S5 (Securing strong green and blue infrastructure), Policy T27 (Reducing health inequalities and promoting health and wellbeing), and Policy DM6 (Sustainable design and construction) all support provision of infrastructure that reduces air pollution. Site Policy SA1 (Chatham Town Centre and Surrounds) will ensure air quality in Central Medway AQMA is addressed through the proposal design. 	<ul style="list-style-type: none"> Despite technological and infrastructure advancements, the proposed development of new homes and employment sites are expected to increase traffic volume and energy demand. Therefore, increased pollutant emissions, particularly NO₂ and PM₁₀, cannot be fully mitigated by MLP policies alone. Continuing the transition to clean technologies will occur over the coming years. The long-term effect on emissions and air quality is likely positive, but short-term negative effects are expected.
 BIODIVERSITY, FLORA & FAUNA	<ul style="list-style-type: none"> Threats or pressures to European sites including Cannock Chase SAC (see the HRA for more details). Threats or pressures to nationally or locally designated and non-statutory biodiversity sites, including from recreational disturbance or increased water/air pollution from visitors to the sites. Fragmentation of the ecological network including priority habitats. 	<ul style="list-style-type: none"> Policy T1 (Promoting high quality design) protects existing trees and aims to establish new landscape features that promote biodiversity. Policy S2 (Conservation and enhancement of the natural environment) requires development proposals to strengthen biodiversity networks and ensure effective mitigation in sensitive locations, including European sites. It promotes conservation, restoration, and enhancement of MCZs, SSSIs, LNRs, LWSs, High Halstow NNR, and ancient woodlands. National requirements mean development proposals must also provide measurable net gain of 10% BNG. 	<ul style="list-style-type: none"> Policy S2 will help mitigate adverse impacts on designated biodiversity sites arising from most development proposed in the MLP. However, the policies may not fully mitigate adverse effects on SSSIs where proposed sites coincide with, or are adjacent to, SSSIs. These sites should be subject to specific consultation with NE. The MLP is expected to result in a residual adverse impact on SSSIs within the Plan area. A potential long-term significant effect on nationally designated biodiversity sites is identified.

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
		<ul style="list-style-type: none"> The Kent and Medway Local Nature Recovery Strategy is likely to encourage opportunities to improve habitat connectivity Policy S3 (North Kent Estuary and Marshes designated sites) requires residential development within the 6km ZOI to contribute to the North Kent SAMMS, and that larger sites beyond the ZOI may need mitigation to offset adverse recreational effects. Policy S5 (Securing strong green and blue infrastructure) encourages the use of GI to provide protection for European, nationally designated, locally designated, and non-statutory biodiversity sites. Policy T10 (Gypsy, Travellers and Travelling Showpeople) and Policy T22 (Marinas and moorings) require development to be away from/have consideration for nationally designated sites. 	<ul style="list-style-type: none"> The MLP policies are likely to mitigate adverse impacts from development proposals which are near locally designated and non-statutory biodiversity assets. The MLP policies will not be expected to fully mitigate adverse effects on sites which coincide with LWSs or are adjacent to a LNR or LWS, where there is potential for habitat loss or degradation associated with designations. They may enhance habitat connectivity and strengthen the resilience of ecological and GI networks against current and future pressure. They support the conservation and expansion of GI coverage, habitat creation, provision of opportunities to improve biodiversity feature connectivity, and promote the protection and enhancement of Kent and Medway LNRS. A long-term positive impact on biodiversity is anticipated.
 CLIMATIC FACTORS	<ul style="list-style-type: none"> Some new development is located in areas of higher fluvial and surface water flood risk where there may be increased risks to human health or damage to properties. Increased GHG emissions due to the construction and occupation of new development and associated traffic. Loss of multi-functional green infrastructure that may reduce resilience to climate change. Reduced viability of flood defences 	<ul style="list-style-type: none"> Policy DM1 (Flood and water management) aims to minimize flood risk with site-specific flood risk assessments with Sequential and Exception testing and providing flood risk management infrastructure. This includes locating development in low-risk areas, maintaining flood risk infrastructure, and contributing to EA's flood risk management programme. It also seeks to minimize surface water flood risk by providing site-specific flood risk assessments and providing flood risk management infrastructure. This includes preparing Surface Water Drainage Strategies such as the implementation of SuDS which replicate greenfield runoff rates. It states that "<i>development that would harm the effectiveness of existing flood defences or prejudice their maintenance or management will not be permitted unless it can be suitably mitigated</i>". This includes continued inspection, maintenance, repair and replacement of existing flood defences. 	<ul style="list-style-type: none"> MLP policies are expected to protect future and existing flood defences from development. There are no anticipated significant adverse effects on flood defence viability associated with development proposed in the MLP. Although relevant MLP policies may be positive in reducing GHG emissions, particularly with energy efficient design and low carbon sources, they may not fully mitigate the impacts of the large growth expected from the Plan. An increase in GHG emissions as a consequence of the proposed development is expected to be a long-term and permanent significant effect. There may be some loss of previously undeveloped land associated with

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
		<ul style="list-style-type: none">Site Policy SA4 (River Waterfront) requires flood mitigation and/or a flood defence wall to enable delivery of allocated sites near the waterfront of north Gillingham.Site Policy SA13 (Frindsbury Peninsula Opportunity Area) highlights emerging Planning Framework that will guide area development, including delivery of strategic flood risk infrastructure.Policy S1 (Planning for climate change) ensures development proposals will include opportunities for adaptation to, and mitigation of, climate change to progress towards achieving net zero carbon in Medway by 2050. The policy promotes effective spatial planning, use of renewable and low carbon technologies and design, delivery of GI, and management of water resources and flood risk. The criteria for S1 are underpinned by Policy DM3 (Air quality), Policy DM6 (Sustainable design and construction), Policy S25 (Energy supply) and Policy T41 (Heat networks), aiming to reduce Medway's carbon footprint.Policy S2 (Conservation and enhancement of the natural environment) encourages development to be located away from biodiversity designations, restoring and enhancing biodiversity across the Plan area.Policy S5 (Securing strong green and blue infrastructure) encourages use of GI to manage surface water flood risk and adapt to the impacts of climate change, helping to conserve and enhance the GI network in the borough. This includes the implementation and management of SuDS.Policy T28 (Existing open space, outdoor sports and play spaces) and Policy DM21 (New open space, outdoor sports and play spaces) both encourage the use of well-managed open spaces to help mitigate surface water flood risk.	<p>development sites. Comprised of or containing greenfield land, however MLP policies seek to conserve and enhance multi-functional green and blue infrastructure across the Plan area.</p> <p>Supporting GI delivery throughout the Plan area means a positive effect on Medway's climate change adaptation is expected.</p>

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
 CULTURAL HERITAGE	<ul style="list-style-type: none"> The introduction of new development may lead to changes in the character and/or setting of designated heritage assets and Conservation Areas New development may also lead to adverse effects on historic character 	<ul style="list-style-type: none"> The Spatial Development Strategy encourages development proposals to use previously developed land and invest in urban areas. Site Policy SA5 (Strood District Centre and Surrounds) ensures development sensitively addresses Rochester Castle and its setting. Policy S8 (Historic environment) supports development that “positively contributes to local distinctiveness and character”, and “preserves or enhances the significance of designated and non-designated heritage assets and their settings.” This includes making sensitive and sustainable reuse of heritage assets, especially those ‘at risk’. Policy S9 (Star Hill to Sun Pier) focuses on conserving and enhancing assets within the identified Heritage Action Zone (HAZ). Policy DM9 (Heritage assets) promotes “<i>a high quality of design which will preserve and seek to enhance the asset’s significance and setting.</i>” A Heritage Statement will be required for development proposals in proximity to heritage assets. No demolition or loss of a heritage asset will be permitted unless exceptional circumstances are demonstrated. Policy DM10 (Conservation areas) only permits development within a CA where it “<i>contributes positively to the conservation and enhancement of the character, appearance and distinctiveness of the area.</i>” Policy DM11 (Scheduled monuments and archaeological sites) does not permit development which adversely impacts SMs or their setting. Policy T1 (Promoting high quality design) encourages developments which respond to the character and appearance of their settings. 	<ul style="list-style-type: none"> Adverse impacts on the character and setting of designated heritage assets including listed buildings and their settings may be mitigated through various MLP policies. A range of plans, programmes and legislation, including the NPPF and local guidance allow protection of heritage assets in line with their significance. The MLP will be expected to help avoid or mitigate potential significant impacts on designated heritage assets arising from proposed development, with a negligible impact identified overall. Adverse impacts on the character and setting of CAs are anticipated to be mitigated through various MLP policies. The MLP is expected to help avoid or mitigate the potential for significant impacts on conservation areas arising from proposed development, with a negligible impact identified overall. Effective design policies such as T1, DM6, S8 and DM9 are likely to deliver positive effects for urban areas.

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
 HUMAN HEALTH	<ul style="list-style-type: none"> A small number of allocations are situated in areas with limited sustainable access to healthcare facilities Exposure to air/noise pollution (from AQMAs/main roads) with implications for health Net loss of public greenspace where some allocations coincide with current open spaces Limited access to PRoW and/or cycle network 	<ul style="list-style-type: none"> Various site allocation policies include provisions of new healthcare hubs, as well as the retention and/or provision of open space and sports facilities. Site Policy SA1 (Chatham Town Centre and Surrounds) will ensure air quality in Central Medway AQMA is addressed through the proposal design. Several site allocation policies include new/enhanced cycle and pedestrian routes, including the Gillingham Greenway within Site Policy SA4 (River Waterfront). Policy S5 (Securing strong green and blue infrastructure) will help to conserve and enhance Medway's multi-functional GI network and greenspaces. Policy DM3 (Air quality) addresses air quality issues across Medway and promotes appropriate design to improve emissions, such as through the installation of electric charging points and low NO₂ boilers. Policies including DM15, T4, T5, T10, T27, S14 and S15 all encourage improved public transport provision and accessibility, which is likely to improve access to healthcare facilities. Policy T26 (Accessibility standards) requires new developments to meet standards for a 15-minute walk or cycle to local amenities. This will improve accessibility to healthcare provision. The Spatial Development Strategy, Policy T26 (Accessibility standards) and Policy DM20 (Cycle parking and storage) aim to reduce reliance on cars and travel needs through facilitating sustainable and active modes of transport. Policy T27 (Reducing health inequalities and promoting health and wellbeing) aims to improve sustainable access to health and wellbeing facilities, reduce health inequalities, and requiring Health Impact Assessments for specific development proposals. It also aims to increase accessibility to 	<ul style="list-style-type: none"> Local Plan policies, such as T26 and T27, will help prevent loss of existing healthcare facilities and improve sustainable access to facilities for residents; However, the policies will not be expected to fully mitigate the restricted healthcare service access for sites in more isolated settlements. The GP-to-patient-ratio in Medway is worse than the national average, with some surgeries not accepting new patients, meaning residents may not be registered with their most local surgery. Limited sustainable access to healthcare facilities is expected to be a medium-term and temporary significant effect. Several MLP policies are expected to reduce the likelihood and extent of potential adverse impacts of air pollution on human health and biodiversity assets. However, the proposed development in the MLP means the likely associated increases in traffic flows and reduction in air quality within an existing AQMA may have residual adverse effects which cannot be fully mitigated through MLP policies. Adverse effects on health as a result of poor air quality across Medway is expected to be a long-term significant effect, although the extent of this impact may reduce over time as clean technologies improve. The MLP policies will be expected to ensure that development proposals do not cause a loss of public greenspace across the borough, leading to a negligible overall effect. Further positive impacts on access to greenspace could be achieved in the longer term, through the provision of

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
		<p>recreational opportunities such as greenspaces. A way of doing this is encouraging improvements to walking, wheelchair, and cycling routes.</p> <ul style="list-style-type: none"> Policy T28 (Existing open space, outdoor sports and play spaces) and Policy DM21 (New open space, outdoor sports and play spaces) encourage adequate open space and greenspace provision, including replacement of losses of open space or greenspace. Policy DM20 sets out required cycle parking standards which will help to facilitate travel via bicycle. 	<p>on-site or off-site GI provisions, dependent on more site-specific context and information.</p> <ul style="list-style-type: none"> The majority of allocated sites are adjacent to existing pedestrian routes and/or cycle paths. Various MLP policies seek to create permeable neighbourhoods and promote cycling and walking, which would likely improve the coverage of, and accessibility to, Medway's pedestrian and cycle networks. An overall positive effect would be likely with regard to pedestrian and cycle access.
 LANDSCAPE	<ul style="list-style-type: none"> Threaten or result in the loss of locally distinctive or sensitive landscapes such as the Kent Downs National Landscape Alteration of landscape character New development may lead to changes in views from local residents or users of the PRoW network Increase urban sprawl and coalescence between settlements 	<ul style="list-style-type: none"> Site Policy SA1 (Chatham Town Centre and Surrounds) and SA5 (Strood District Centre and Surrounds) require views analysis to inform development. Site Policy SA8 (Hoo St Werburgh and Chattenden) requires a strategic landscape corridor to separate of Hoo and Chattenden. Site Policy SA9 (High Halstow) avoids coalescence with nearby settlements using landscape buffers. Policy S4 (Landscape protection and enhancement) requires development proposals to demonstrate their response to key sensitivities and qualities of the surrounding landscape, including the Kent Downs National Landscape. It also requires development to conserve and enhance Medway's local landscape character and distinctiveness, such as North Kent Marshes. Proposals are encouraged to be in areas of lower landscape sensitivity and to consider visual landscape attributes. Policy S5 (Securing strong green and blue infrastructure) encourages development proposals to reflect local character by providing multi-functional GI. 	<ul style="list-style-type: none"> Various MLP policies (specifically Policy S6) protect nationally designated landscapes. Plans, programmes and legislation including the NPPS protect nationally designated landscapes in line with their significance. The MLP will be expected to help avoid/mitigate the potential for significant impacts on nationally designated landscapes from proposed development, with a negligible impact identified overall. Due to the proposed development's scale, with a large proportion in previously undeveloped locations, the policies are not expected to fully mitigate the potential impacts on landscape character and an adverse effect is anticipated. Alteration of landscape character is a long-term, permanent, significant effect. There is potential for a cumulative adverse effect on landscape character resulting from the proposed development. The MLP policies provide some protection for visual amenity and views

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
		<ul style="list-style-type: none"> Policy S6 (Kent Downs National Landscape) seeks to ensure developments within or in the setting of the National Landscape conserve and enhance its character. This includes Ranscombe Farm Country Park (within the National Landscape) and may also apply to Capstone Farm Country Park, due to its proximity. Policy S7 (Green Belt) aims to maintain a strong Green Belt within Medway and would ensure new development is only permitted in the Green Belt in exceptional circumstances. Policy T1 (High Quality Design and Amenity) will ensure development is appropriate to its surroundings and informed by Landscape and Visual Impact Assessment. It also seeks to retain urban/rural distinctiveness through containing settlements to avoid coalescence. The Spatial Development Strategy encourages retention of separation between urban Medway and the Hoo Peninsula through green corridors between the areas. 	<p>and may help mitigate adverse impacts, but it is likely a residual impact will remain due to the large proportion of development being proposed on previously undeveloped sites with regard to the PRoW and existing properties. An adverse residual impact of alteration of views for a number of allocated sites is anticipated. Alteration of views is likely to be a long-term and permanent minor adverse effect.</p> <ul style="list-style-type: none"> Various MLP seek to minimize impacts on the countryside and maintain separation between settlements with the Green Belt and open countryside. However, as some new development is rural, the Local Plan policies are not expected to fully mitigate these impacts, and a residual adverse effect is anticipated. An increased risk of urbanisation of the countryside and coalescence is a long-term and permanent significant effect,
 POPULATION & MATERIAL ASSETS	<ul style="list-style-type: none"> The MLP needs to ensure the provision of housing and employment opportunities to meet local need A small number of allocations are situated in areas with limited sustainable access to services and facilities Increased pressure on local services from new development Some development is located in deprived areas where there are inequalities to be addressed 	<ul style="list-style-type: none"> The Spatial Development Strategy allocates 21,194 new dwellings for the Plan period. Site Policy SA14 (Employment Sites) sets out a range of employment land uses and floorspace to be delivered within the Plan period including 324,450m² at MedwayOne (former Kingsnorth Power Station). Policy S10 (Economic strategy) will “seek to boost Medway’s economic performance, securing a range of jobs for its workforce,” which includes improving the range of employment sites within Medway, which is likely to compensate for any loss of employment floorspace. Policy S15 (Town centres strategy) supports extended retail provision and the development of in- 	<ul style="list-style-type: none"> In order to meet the identified housing need, the Local Plan proposed to deliver 21,194 new dwellings. Policies in the Plan set out requirements to provide an appropriate mix of housing types and tenures, seeking to meet the needs of different groups, including older people. A positive effect on housing provision is anticipated. The plan provides sufficient land for employment sites that meet the needs of different types of businesses. The strategy recognises the potential to realise the strategic economic role of sites such as Grain and Kingsnorth in

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
	<ul style="list-style-type: none"> Increased household waste generation Potential sterilisation of mineral resources 	<ul style="list-style-type: none"> centre and edge of centre locations for employment outside of designated employment areas. Policy DM17 (Grain Branch) aims to safeguard land for a potential railway station and will not permit development that may compromise new rail infrastructure in this area. Policy DM18 (Transport assessments, transport statements and travel plans) requires all development proposals that will generate a significant amount of movement to be supported by a Transport Assessment or Statement, or commitment to provide one. Policy DM23 (Waste prevention) encourages design principles that minimise waste and locally produced and recycled resources. Policy T2 (Housing mix) aims to ensure that residential developments meet the identified local housing needs, supporting the current and future requirements of the population in terms of housing type and size, as well as providing specialist accommodations for those with particular needs. Policy T3 (Affordable housing) sets out the requirements to deliver affordable housing in urban and rural communities, to ensure that suitable residential development is provided to meet the social and economic needs of the population. Policy T26 (Accessibility standards) requires all proposals to be accessible to a secondary school or social space via a 15-minute bus journey. Policy T30 (Safeguarding mineral resources) ensures development is permitted only where it would not intervene with current or potential extraction of valuable mineral resources. Policy T31 (Safeguarding of existing mineral supply infrastructure) safeguards existing mineral supply infrastructure from development that may limit their operation. 	<p>growing sectors. A positive effect on employment provision is anticipated.</p> <ul style="list-style-type: none"> The MLP policies are expected to improve access to local services and facilities for most sites through improved transport networks, developer contributions to services, and new service provision. However, access could remain limited within some rural sites, although the Travel Plans will potentially address this. A residual negligible impact is identified for access to local services. The Waste Needs Assessment (WNA) found sufficient existing consented capacity to meet requirements for recycling, composting and inert waste over the Plan period, but a shortfall in non-inert waste to landfill. The construction and occupation of new homes and businesses could cumulatively increase non-inert waste production and potentially impact the capacity of existing waste facilities. The cumulative impact of increased waste generation on the capacity of waste management facilities could potentially be a medium-term, but potentially temporary, significant effect. Policies T30 and T31 are expected to ensure that potential impact on safeguarded minerals is avoided or minimised. A minor positive effect on

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
		<ul style="list-style-type: none"> Policies T34 (Safeguarding of existing waste management facilities) and T35 (Provision of additional waste management capacity) safeguard current waste infrastructure and increase its capacity for waste management. Policy T37 (Other recovery) supports provision of energy from waste facilities where waste cannot be reused or recycled. Policies including DM15, T4, T5, T10, T27, S16 and S17 all encourage development to be in areas accessible to public transport whilst encouraging co-location of services. This includes improving bus links. 	mineral resource conservation will be expected.
	<ul style="list-style-type: none"> Direct loss of soil resources due to construction of new development which contains previously undeveloped land. The MLP could result in the loss of up to c.1,110ha of previously undeveloped land, of which c.980ha is potential BMV land¹⁹. 	<ul style="list-style-type: none"> The Spatial Development Strategy encourages development proposals to make use of previously developed land, locating development away from greenfield land with high value soil. Policy S4 (Landscape protection and enhancement) aims to provide local nature recovery networks and improve habitat connectivity, consequently areas of BMV soil. Policy S5 (Securing strong green and blue infrastructure) will help conserve and enhance the borough's GI network, including BMV soil. Policy T14 (Rural economy) supports employment development in the countryside that does not lead to significant loss of high-grade agricultural land and can demonstrate that locations of lower agricultural land values are not suitable. 	<ul style="list-style-type: none"> The proposed allocations would cumulatively result in the loss of a significant amount of previously undeveloped land. The loss of permeable soils has potential to increase the risk of flooding and result in a loss of biodiversity across the borough. Loss of soil can also result in an increase in soil erosion and have subsequent impacts on air quality and agricultural yield. Therefore, a residual adverse effect will be expected. The loss of previously undeveloped land, a large proportion of which could include BMV land, is

¹⁹ Please note this figure is based on gross site areas and does not take into account net developable areas excluding new open space / green infrastructure provision or sites which are already partially developed.

Additionally, in absence of a detailed subgrade assessment distinguishing between Grade 3a and 3b, the total area of BMV land has been calculated on the assumption that all land classified as Grade 3 is Grade 3a. This approach may overestimate the actual extent of BMV land. A more accurate classification would require site-specific ALC survey data.

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
			<p>expected to be a long-term and permanent significant adverse effect.</p>
 WATER	<ul style="list-style-type: none">• Reduction in water quality and ecosystem services due to increased run-off of pollutants• Increased demand for water and wastewater management due to new development	<ul style="list-style-type: none">• Policy DM1 (Flood and water management) promotes efficient water usage and will ensure that adequate wastewater infrastructure is provided for new development. Development will be required to be in accordance with the Water Resource Management Plans published by South East Water and Southern Water to ensure public water supplies are maintained. Additionally, the policy will ensure that all new development integrates the requirements of the Thames River Basin District Management Plan²⁰ including to improve water quality.• Policy DM1 and Policy S5 (Securing strong green and blue infrastructure) encourage the preparation of Surface Water Drainage Strategies including the implementation of multi-functional SuDS to provide benefits for water quality.• Policy T40 (Wastewater treatment) promotes effective wastewater disposal in line with regulatory provisions.	<ul style="list-style-type: none">• While MLP policies and consultation with water companies will help reduce water quality impacts, development may still increase sewage discharge into rivers, requiring further monitoring. A residual adverse effect on water quality and ecosystem services remains possible, in line with the precautionary principle. Deterioration in water quality and ecosystem services has the potential to be a long-term but potentially temporary significant effect.• National and MLP policies, along with broader water management frameworks, aim to improve water efficiency and mitigate adverse effects. Whilst it is likely that these measures will mitigate any adverse effects, at the time of writing, no data has been made available to confirm whether wastewater treatment works (WwTW) that serve Medway will have capacity for the projected growth, or whether sufficient water resources are available to support water supply for new development. Uncertainty remains regarding the potential for increased pressure on water supply and

²⁰ Environment Agency (2022). Thames River Basin District Management Plan. Available at: www.gov.uk/guidance/thames-river-basin-district-river-basin-management-plan-updated-2022 [Date accessed: 26/03/25]

Sustainability theme	Potential Impacts of the MLP	Mitigating MLP policies	Summary of residual effects
			wastewater management infrastructure.

DRAFT

Conclusions

N82. Overall, the MLP is expected to deliver a range of positive outcomes, including enhanced biodiversity and ecological networks, improved GI and public greenspace, the provision of needed housing and employment opportunities, and the conservation of mineral resources. Overall, it supports sustainable development while promoting climate resilience and economic growth.

N83. Identified adverse effects largely relate to the potential for the growth proposed in the MLP to cumulatively lead to an increase in GHG emissions, air and water pollution, and the loss of soil resources. These impacts include issues that the MLP cannot fully address alone, such as the increased frequency of storm events linked to broader national and international climate trends. Additionally, the Plan may contribute to residual negative effects on biodiversity, landscape character, urban sprawl, and access to healthcare in rural areas, many of which are long-term and cannot be entirely mitigated through local policy measures.

N84. It will be important to ensure effective monitoring is in place so that Medway Council can respond to these effects during the lifetime of the MLP.

Monitoring

N85. Monitoring proposals are set out in **Table N.7.2** for Medway to consider in the implementation of the MLP.

Table N.7.2: Proposals for monitoring adverse sustainability impacts of the MLP

Theme/ SEA Regulations	Indicator	Scale and frequency	Target
Air	Concentration of NO ₂ and PM ₁₀	Annually, Plan area wide	Decrease
Air	Road network performance	Bi-annually, Plan area wide	Decrease
Air	Number of vehicle trip credits (i.e. vehicle trip generation from new development)	Bi-annually, Plan area wide	Decrease
Air	Rates of public transport uptake	Annually, Plan area wide	Increase
Biodiversity, flora and fauna	Percentage of SSSIs in favourable condition	Annually, Plan area wide	Increase
Biodiversity, flora and fauna	Number of planning approvals granted contrary to the advice of Natural England	Annually, Plan area wide	Zero
Biodiversity, flora and fauna	Percentage loss of the ecological network	Annually, Plan area wide	Zero
Biodiversity, flora and fauna	Quality and extent of priority habitats	Annually, Plan area wide	Increase
Biodiversity, flora and fauna	Uplift in biodiversity net gain units within Medway	Annually, Plan area wide	Increase
Biodiversity, flora and fauna	Implementation of measures from the North Kent SAMMS	Various	Various
Climatic factors	CO ₂ emissions per capita	Annually, Plan area wide	Decrease

Theme/ SEA Regulations	Indicator	Scale and frequency	Target
Climatic factors	Percentage of energy generated from renewable sources	Annually, Plan area wide	Increase
Climatic factors	Number of properties at risk of flooding	Annually, Plan area wide	Decrease
Climatic factors	Extent of surface water flood risk	Annually, Plan area wide	Decrease
Climatic factors	Fluvial/tidal flood risk along the River Medway	Annually, Plan wide area	Decrease
Cultural heritage	Number of conservation area appraisals	Annually, Plan area wide	Increase
Cultural Heritage	Number of heritage assets identified as 'heritage at risk'	Annually, Plan area wide	Decrease
Human health	Percentage of physically active adults	Bi-annually, Plan area wide	Increase
Human health	Number of GP surgeries	Annually, Plan area wide	Increase
Human health	Hectares of accessible open space per 1,000 population	Annually, Plan area wide	Increase
Landscape	Quantity of development in sensitive landscapes	Annually, Plan area wide	Zero
Landscape	Quality and extent of green infrastructure	Annually, Plan area wide	Increase
Population and material assets	Number of affordable housing completions	Annually, Plan area wide	Increase
Population and material assets	Percentage of economically active residents	Annually, Plan area wide	Increase
Population and material assets	LSOAs in Medway within the 10% most deprived in Great Britain	Every 3 to 4 years, Plan area wide	Decrease
Population and material assets	Quantity of household waste sent to landfill	Annually, Plan area wide	Decrease
Population and material assets	Quantity of commercial and industrial waste recycled	Annually, Plan area wide	Increase
Population and material assets	Area of safeguarded mineral resources	Annually, Plan area wide	Maintain
Soil	Number of dwellings built on previously developed or brownfield land	Annually, Plan area wide	Increase
Soil	Area of contaminated land remediated	Annually, Plan area wide	Increase
Water	Number of planning permissions granted contrary to Environment Agency advice	Annually, Plan area wide	Zero
Water	Number of waterbodies classified as 'good' ecological status	Annually, Plan area wide	Increase
Water	Number of overflow events of untreated sewage discharges into rivers	Annually, Plan area wide	Zero
Water	Water efficiency in new homes	Annually, Plan area wide	Increase
Water	Water availability for extraction	Annually, Plan area wide	Increase

Consultation and next steps

N86. The Regulation 19 SA Report will be published alongside the Publication Version of the Medway Local Plan.

N87. A minimum of a six-week period of consultation will be undertaken by Medway Council to offer statutory consultees, stakeholders, organisations and individuals an opportunity to submit representations regarding the MLP, as well as supporting evidence including this SA Report.

N88. Following this round of consultation, all comments will be analysed by the plan makers as part of the ongoing plan making process. Further stages of SA will be prepared if and when necessary.

DRAFT



Lepus Consulting
Eagle Tower,
Montpellier Drive,
Cheltenham
Gloucestershire GL50 1TA

t: 01242 525222
w: www.lepusconsulting.com
e: enquiries@lepusconsulting.com